

## FLOOR FINISHES: CORRECTIONS AND CLARIFICATIONS

FINISH FLOOR TRANSITIONS BETWEEN SPACES SHALL MATCH THOSE IN EXISTING ADJACENT ROOMS AND CORRIDORS.

### LOCATIONS: CORRIDORS, ADMINISTRATION (R01) AND RECEPTION OFFICE (R04)

LUXURY VINYL PLANK (LVP): "TO MARKET" OZOGrip - FAST TRACK, 5MM LOOSE LAY LUXURY VINYL PLANKS OR EQUAL. INSTALL PER MANUFACTURERS RECOMMENDATIONS. VERIFY SIZE, COLOR AND FINISH WITH OWNER. MATCH IN CORRIDORS IF POSSIBLE.

### LOCATIONS: EXAM ROOMS (R02) (R03)

RUBBER SHEET FLOORING (RBS): noraplan environcare™ 3.0 mm sheet resilient floor covering OR EQUAL. INSTALL PER MANUFACTURERS RECOMMENDATIONS. VERIFY COLOR WITH OWNER.

### LOCATIONS: RECEPTION (R05), LOBBY AND CORRIDORS

CONCRETE SURFACE FINISH:

IN ALL AREAS WHERE EXISTING CONCRETE IS REPAIRED, PATCHED, OR REFINISHED, THE SURFACE SHALL BE GROUND, POLISHED, AND SEALED TO MATCH ADJACENT FINISH. FINAL APPEARANCE SHALL BE UNIFORM AND CONSISTENT WITH SURROUNDING SURFACES.

ROOM FINISH SCHEDULE								
NUMBER	ROOM NAME	FLOOR FINISH	BASE	WALL MATERIAL	WALL FINISH	CEILING HEIGHT	CEILING FINISH	AREA, (SQ FT)
R01	ADMINISTRATION	VINYL PLANK	TOP SET BASE	GYPSUM BOARD	ENAMEL PAINT	109"	ACOUSTICAL CEILING TILES	127
R02	EXAM 1	RUBBER SHEET	TOP SET BASE	GYPSUM BOARD	ENAMEL PAINT, 4' HIGH FRP	120"	ACOUSTICAL CEILING TILES	129
R03	EXAM 2	RUBBER SHEET	TOP SET BASE	GYPSUM BOARD	ENAMEL PAINT, 4' HIGH FRP	120"	ACOUSTICAL CEILING TILES	129
R04	RECEPTION OFFICE	VINYL PLANK	TOP SET BASE	GYPSUM BOARD	ENAMEL PAINT	120"	ACOUSTICAL CEILING TILES	177
R05	RECEPTION	SMOOTH CONCRETE	TOP SET BASE	GYPSUM BOARD	ENAMEL PAINT		.	247
TOTALS:								809

## SHEET A-4



### FLOOR FINISH CORRECTION - RECEPTION OFFICE, ROOM (R04)

- Floor finish in the reception office (R04) shall be vinyl plank flooring.

- The following notes on **SHEET A-2** is to be disregarded.

#### CARPET

Mohawk Drifted Ground Tile 12" x 36" or equivalent.

#### HARD SURFACE FLOORING:

Armstrong Flooring DecoArt Carlon Inlaid Commercial Sheet Flooring or equivalent.

## ADDENDUM 5 - FLOOR FINISHES

#### PROJECT ADDRESS:

**Westside Health Care District**  
100 E. North Street  
Taft, CA. 93268

#### PROJECT CONTACT:

**Ryan Shultz, MSHCA**  
Executive Director

(661) 765-7234 Office  
(661) 203-5757 Cell  
rshultz@wshcd.org

PAGE 1 of 1  
DATE: 7/10/2025

# REQUEST FOR INFORMATION (RFI)

<b>PROJECT:</b>	Building "A" Remodel and Building Renovations	<b>RFI NO.:</b>	PB-006
<b>OWNER:</b>	West Side Health Care District	<b>DATE:</b>	07/08/2025
<b>CONTRACTOR:</b>	Black/Hall Construction, Inc. P.O. Box 445 Taft, CA 93268		

<b>DRAWING REFERENCE:</b>	<b>SPECIFICATION REFERENCE:</b>
<b>BRIEF TITLE:</b> Finish Material	

**DESCRIPTION OF CLARIFICATION REQUIRED (attach sheets as necessary):**

1. As per **Sheet A-4 Room Finish Schedule**, we are to provide **Vinyl Plank** in the **Administration area** and **Rubber Sheet** in the **Exam Room**. However, the **Finish Specifications provided on Sheet A-2** indicate **Carpet and Sheet Vinyl** in these areas, which does not match the Room Finish Schedule. Could you please confirm which finish takes precedence and whether any specific **manufacturer, style, and color** have been specified? Or should we proceed with **industry-standard** selections?
2. Could you please confirm the type of concrete finish required in the Reception and Reception Office areas? Specifically, is the finish intended to be Polished Concrete or Sealed Concrete?

**CONTRACTOR'S PROPOSED SOLUTION:**

See attached addendum 5

<b>INITIATOR:</b> Black / Hall Construction Inc.	<b>SIGNATURE:</b>
<b>DATE RESPONSE REQUIRED:</b> ASAP	