

DOCUMENT 00 9111

ADDENDUM NO. THREE
07/10/2025

COUNTY OF KERN
GENERAL SERVICES

BVARA RPP
13601 Ironbark RD., Bakersfield, CA 93311
Project No. 1650.7087-23.

Drawings

Item No. 1: On drawing LP-03, delete the California Conservation Corp (CCC) Coordination notes and add the following to drawing LP-03.

“The California Regional Park Program (RPP) is funding this project with a grant. The RPP Grant requires that the General Contractor provide employment opportunities in this project. As stated in our agreement with the RPP the following opportunities shall be included in this project:

- *15 Corps members - The local Fresno Center Conservation Corps (CCC) has determined it is feasible to assist with tree planting. This will provide a meaningful employment opportunity for corps members in the Central Valley. Corps work will also include the following:*
 - *Total Cost for services shall be included in the project's base bid. (CCC provided a quote of \$31,200 to the County on 12/1/2022). The Contractor shall contact California Conservation Corps for updated quotation for the services described below.*
 - *Planting 50 – trees as shown and detailed on the drawings*
 - *Excavating plant pits*
 - *Installing trees*
 - *Installation of tree staking*
 - *Restoration of excavation*

The county will contact the Project Manager of the Fresno Center and coordinate the planning of CCC involvement in this project with the General Contractor who is awarded the bid:
Miguel Diaz, Conservationist Supervisor (Project Manager)
Email: Miguel.Diaz@ccc.ca.gov
Phone: (559) 360-0019

- *The general contractor and landscape sub-contractor shall be responsible for coordinating and managing all activities on site and labor performed by CCC members. The landscape contractor shall ensure installation complies with the plans and specifications. The general contractor and/or landscape contractor shall provide all tools and equipment necessary for proper execution of assigned work. The landscape contractor shall provide maintenance for the CCC installed trees during construction and the landscape maintenance period. Owner shall replace dead or dying trees through no fault of the general contractor and/or landscape contractor.”*

Item No. 2: On drawing E-03 detail 07, the transformer shall be mounted a minimum of 18" above grade (measured to bottom of XFMR/Top mount support base). County Representative to direct exact placement in the field.

Specifications

Item No. 3: Section 13 3423: Delete items 2.1C and 2.1D from the specification section 13 3423.

The following Addenda were issued, modifying the Project Manual:

Addendum No. 1, issued on **06/20/2025**

Addendum No. 2, issued on **07/01/2025**

Addendum No. 3, issued on **07/10/2025**


Cesar Juarez, Supervising Engineer
Construction Services Division

Contractor

Signature

Date

Name/Title

END OF DOCUMENT