

SOILS ENGINEERING, INC.



**GEOTECHNICAL INVESTIGATION REPORT
FOR THE
NEW DISTRICT OFFICE AND MOT YARD
6327 ZEPHYR LANE
BAKERSFIELD, KERN COUNTY, CA**

Prepared for:

**Fairfax School District
1500 S Fairfax Road
Bakersfield, CA 93307**

By:

**SOILS ENGINEERING, INC.
SEI File No. 23-19257
November 21, 2023**


**On Man Lau, P.E., G.E.
Engineering Manager**



COPYRIGHT: All reports issued by the consultant are protected under copyright. Notwithstanding the fact that the Copyright in this document, and each portion contained herein, is the sole property of Soils Engineering, Inc., and without waiving or in any way transferring said Copyright, Soils Engineering, Inc. hereby grants Fairfax School District the nonexclusive right to copy, reproduce, and distribute this report for his/her own non-commercial, in-house use.

TABLE OF CONTENTS

INTRODUCTION 3

SITE INFORMATION

A. SITE LOCATION AND CONDITIONS 4
B. GEOLOGIC SETTING 4
C. SUBSURFACE CONDITIONS 4
D. GROUNDWATER 5
E. SEISMIC DESIGN VALUES 5

EARTHWORK RECOMMENDATIONS

A. COMPACTION AND OPTIMUM MOISTURE 7
B. STRIPPING 7
C. GROUND SURFACE PREPARATION 7
D. ENGINEERED FILL 9
E. IMPORTED FILL 9
F. DRAINAGE 10
G. SLOPES 10

FOUNDATION RECOMMENDATIONS 11

MODULUS OF SUBGRADE REACTION 12

LATERAL EARTH PRESSURES 12

SOIL CORROSIVITY 13

SLABS-ON-GROUND 14

PAVEMENT FIELD INVESTIGATION & DESIGN DATA 14

LIMITATIONS, OBSERVATIONS AND TESTING 15

REVIEW OF EARTHWORK OPERATIONS 16

APPENDIX A, "GUIDE SPECIFICATIONS FOR EARTHWORK" 17

APPENDIX B, "FIELD INVESTIGATION" 23

APPENDIX C, "SOILS TEST DATA" 24

APPENDIX D, "SEISMIC DESIGN INFORMATION" 26

GEOTECHNICAL INVESTIGATION REPORT
FOR THE
NEW DISTRICT OFFICE AND MOT YARD
6327 ZEPHYR LANE
BAKERSFIELD, KERN COUNTY, CA

By:

SOILS ENGINEERING, INC.
SEI File 23-19257
November 21, 2023

INTRODUCTION

At your request, Soils Engineering, Inc. has prepared this Geotechnical Investigation for the subject site. This report includes recommendations for the site preparation and grading and for foundation design.

Appendix A, "Guide Specifications for Earthwork," is providing as supplement to Section I, "Earthwork," in the recommendations of the report.

Appendix B, "Field Investigation," contains a boring location map, Figure 1, and Logs of Test Borings, Figures 2 through 6.

Appendix C, "Soils Test Data," contains tabulations of laboratory test data.

Appendix D, "Seismic Investigation," contains information provided by EQFAULT, and the SEAOC.

We hope this provides the information you require. If you have any questions regarding the contents of our report, or if we can be of further assistance, please contact us.

Respectfully submitted,
SOILS ENGINEERING, INC.

SITE INFORMATION

A. SITE LOCATION AND CONDITIONS

The New District Office and MOT Yard Project is located at 6327 Zephyr Lane, Bakersfield, CA (site). The proposed improvements for the project site at this time are to construct a new district office, MOT yard, parking areas, and bus parking stalls. The project site is located immediately west of Zephyr Elementary School. We anticipate the proposed buildings will be constructed of a combination of concrete, wood, masonry and/or metal framing. It is also anticipated that the parking and/or drive aisles will consist of aggregate base and hot mix asphalt. Currently the site is vacant land with seasonal vegetation within the project area. C-Trains are on the southeastern portion of the site. A drive aisle is present that leads to the west side of Zephyr Lane Elementary School. Site borders include residential properties west and southwest, a drainage sump and solar array to the south, Zephyr Lane Elementary School to the east, and Zephyr Lane and residential properties to the north.

The majority of the project area appears to be relatively flat dirt ground surfaces.

B. GEOLOGIC SETTING

According to the California Department of Conservation's Geologic Atlas of California, Bakersfield Sheet, and the 2010 Geologic Map of California, the project site is situated on Pleistocene - Holocene marine and nonmarine (continental) sedimentary rocks (Q). Based on the California Department of Conservation's Geological Survey maps, the site is not located in an Alquist-Priolo (earthquake fault) Special Study Zone. Nearby active earthquake faults include the following:

Kern Front.....	8.5 miles/ 13.6 kilometers
White Wolf	13.2 miles/ 21.3 kilometers
Pleito Thrust	24.3 miles/ 39.1 kilometers
Garlock (West).....	32.4 miles/ 52.2 kilometers
San Andreas – Whole M-1a and other segments.....	35.9 miles/ 57.7 kilometers
Big Pine	36.5 miles/ 58.7 kilometers
San Gabriel.....	43.8 miles/ 70.5 kilometers

Major fault systems and their distances from the site are given in the EQFault Summary attached in Appendix D. The largest estimated peak site acceleration, based on deterministic methods, is 0.3014-g from a magnitude 7.3 earthquake on the White Wolf fault approximately 13.2 miles away.

C. SUBSURFACE CONDITIONS

Subsurface soils encountered in our field investigation consisted mainly of soil layers of a dry to moist, stiff to hard, and medium plasticity Sandy Clays and damp, medium dense to dense, and cohesive Clayey Sand. An olive brown, damp to moist, and fine grained Poorly Graded Sand was encountered from 15' to 17' below the ground surface in B-1. These soils are classified as ML, SC, and SP, respectively, in the Unified Soil Classification System (USCS).

Testing performed in our laboratory showed an Expansion Index (EI) of 5, which is indicative of non-expansive soils. Expansive soils are defined in the 2022 California Building Code (CBC), Section 1803A.5.3. Soils are considered to be expansive when the EI result is greater than 20, per ASTM D4829, Expansion Index of Soils.

The majority of the near surface soils should provide adequate support for the proposed modular structure provided that a portion of the surface soils are excavated and compacted as outlined in the earthwork recommendations of this report. Detailed descriptions of various soils encountered during our field investigation are shown on Figures 2 through 6 in Appendix B, "Field Investigation." A "Key to Symbols" legend describing the symbols in the boring logs is also attached.

D. GROUNDWATER

Groundwater was not encountered during the field investigation. According to the California Department of Water Resources SGMA Data Viewer, groundwater in the vicinity is approximately 252 feet below ground surface in the Spring of 2023.

E. SEISMIC DESIGN VALUES

The seismic design values presented in the table below are based on the 2022 CBC. The Site Class for the proposed project is a Site Class "D" in accordance with the 2022 CBC §1613.2.2, soil boring data and local knowledge. The site is not located within an Alquist-Priolo (earthquake fault) Special Study Zone.

GEOTECHNICAL INVESTIGATION REPORT
New District Office and MOT Yard
6327 Zephyr Lane, Bakersfield, CA 93307

SEI File No. 23-19257
November 21, 2023
Page 6

SEISMIC DESIGN CRITERIA		VALUE	SOURCE
Risk Category		II	2022 CBC Table 1604.5 or 1604A.5
Site Class		D	2022 CBC § 1613.2.2 or 1613A.2.2; ASCE 7-16 Table. 20.3-1; Site Specific Soils Report
Mapped MCE_R Spectral Response Acceleration, short period	S_s	0.962g	SEAOC-OSHDP software; 2022 CBC Figure 1613.2.1(1)
Mapped MCE_R Spectral Response Acceleration, at 1-sec. Period	S_1	0.345g	SEAOC-OSHDP software; 2022 CBC Figure 1613.2.1(2)
Site Coefficient	F_a	1.115	SEAOC- OSHDP software; 2022 CBC Table 1613.2.3(1) or 1613A.2.3(1)
Site Coefficient	F_v^*	1.955*	2022 CBC Table 1613.2.3(2) or 1613A.2.3(2)
Adjusted MCE_R Spectral Response Acceleration, short period, $F_a * S_s$	S_{MS}	1.073g	SEAOC- OSHDP software; 2022 CBC § 1613.2.3 or 1613A.2.3
Adjusted MCE_R Spectral Response Acceleration, 1-sec. period, $F_v * S_1 * 1.5$	S_{M1}^*	1.012g*	2022 CBC § 1613.2.3 or 1613A.2.3, ASCE 7-16, Supplement 3, § 11.4.8
Design Spectral Response Acceleration, short period, $2/3 * S_{MS}$	S_{DS}	0.715g	SEAOC- OSHDP software; 2022 CBC § 1613.2.4 or 1613A.2.4
Design Spectral Response Acceleration, 1-sec. period, $2/3 * S_{M1}$	S_{D1}^*	0.674g*	2022 CBC § 1613.2.4 or 1613A.2.4
Peak Ground Acceleration for Max. Considered Earthquake (MCE_G)	PGA	0.415g	SEAOC- OSHDP software; ASCE 7-16 Fig 22-9
Site Coefficient, $F_{PGA} = 1.185$, $F_{PGA} * PGA$	PGA_M	0.492g	SEAOC- OSHDP software; ASCE 7-16 § 11.8.3.2
Seismic Design Category, short period		D	2022 CBC § 1613.2.5
Seismic Design Category, 1second period *		D*	2022 CBC § 1613.2.5
* The project Structural Engineer shall confirm that a ground motion hazard analysis is not required in accordance with ASCE 7-16 § 11.4.8-Exception 2. The values tabulated above for S_{M1}, S_{D1}, and the Seismic Design Category/1-second period are based on the site coefficient, F_v, interpolated from 2022 CBC Table 1613.2.3(2) or 1613A.2.3(2). The use of that table is predicated on the above referenced Exception 2 being applicable for the site and the structure(s). The project Structural Engineer or designer shall confirm that the above referenced Exception 2 is applicable. Where the above referenced Exception 2 does not apply, the values for F_v, S_{M1}, S_{D1}, and for the Seismic Design Category/1-second period may not be applicable for the site and structure(s).			
MCE_R = Maximum Considered Earthquake (risk targeted) MCE_G = Maximum Considered Earthquake (geometric mean)			

EARTHWORK RECOMMENDATIONS

"Earthwork Specifications," in Appendix A are provided for general guidance in preparing site grading plans. In addition, the following specific recommendations are provided and supersede the latter wherever discrepancies may exist:

A. COMPACTION AND OPTIMUM MOISTURE

Unless otherwise specified herein, the terms, "Compaction," or "Compacted," wherever used or implied within this report should be interpreted as compaction to 90 percent of the maximum density obtainable by ASTM Test Method D1557. The term, "Optimum Moisture," wherever used or implied within this report, should be interpreted as that obtained by the above-described test method.

B. STRIPPING

Prior to site grading, existing ground surfaces should be stripped of surface vegetation and high-volume root masses. A stripping depth of one to three inches is generally adequate. Stripped material shall not be used as engineered fill or blended with or incorporated into any materials which will underlie any structures or other improvements on the project. Removal of trees or other large plants shall include all roots larger than $\frac{3}{4}$ " diameter. If necessary, root remnants are to be removed by hand-picking. Remove existing structures and improvements, including within the limits of grading or as depicted in the project documents.

C. GROUND SURFACE PREPARATION

Proposed Structure Areas:

Ground surfaces in the proposed building area should be compacted in accordance with the following procedures:

1. Excavate earth material in the proposed building area to a minimum depth of four (4) feet below existing grade or one foot below bottom of the footing elevation, whichever is greater.
2. The bottom of the excavation shall be reviewed by the soil engineer or his or her representative prior to any backfill operations. *The top eight inches of materials exposed at the bottom of the excavation shall be scarified and compacted to a minimum of 90 percent of ASTM D-1557.*
3. Moisten soils to near the optimum moisture or to a moisture consistent with effective compaction and soil stability. Compact moistened soils to a minimum of 90 percent of the maximum density obtained by ASTM Test Method D1557.
4. Work to lines at least five (5) feet beyond the outside edges of exterior footing and two feet beyond pavement edges except where excavation may undermine or damage adjacent structures or utilities.

Review of Excavation Bottoms:

Prior to placement of backfill, excavation bottoms shall be reviewed for indications of loose-fill, discoloration, or loose, compressible, native materials. Where these are encountered, they should be excavated and removed, or excavated and compacted as directed by the geotechnical engineer. Excavation of native soils shall continue in vertical increments of one foot until relative compaction tests taken at the bottom of the working surface (excavation bottom) equal or exceed 80 percent relative compaction. Fill placement in excavations shall not proceed until the geotechnical engineer or his or her representative on the site has reviewed, tested as described above and accepted materials exposed at the bottom of the excavation.

Concrete Flatwork, Slab-on-Grade, and Sidewalk Areas:

Ground surfaces to receive concrete flatwork and sidewalk should be over-excavate two foot below existing grade or two feet below bottom of the concrete. The bottom of the over-excavation should be scarified and compacted to a minimum depth of 8 inches. The upper two feet of the finish grade must be non-expansive material. The on-site expansive clayey soil is not suitable for the upper two feet of the finish grade.

Engineered fill placed in proposed pavement areas should conform to the requirements of section 5.4, "Placing, Spreading and Compacting Fill Materials," of Appendix A.

Compaction in proposed concrete flatwork and sidewalk area should be a minimum of 90 percent of the maximum density as obtained to ASTM Test Method D1557 and should extend to a minimum of two feet beyond the outside edges of pavements.

Utility Lines:

Backfill for utility lines traversing areas proposed for facilities, pavements, concrete slabs-on-grade, or areas to receive engineered fill for future construction should be compacted in accordance with the same requirements for adjacent and/or overlying fill materials.

Compaction should include haunch area, spring line and from top of pipe to finished subgrade. The haunch area up to one foot above the top of the pipe should be backfilled with "cohesionless" material.

Cohesionless native materials may be used for trench and pipe, or conduit backfill. The term "cohesionless," as used herein, is defined as material which, when dry, will flow readily in the haunch areas of the pipe trench.

Pipe backfill materials should not contain rocks larger than two inches in maximum dimension. Where adjacent native materials exposed on the trench bottoms contain protruding rock fragments larger than two inches in maximum dimension, conduits and pipelines should be laid on bedding consisting of clean, cohesionless sand (SP), in the Unified Soils Classification System.

Compaction Requirements – where not otherwise specified in our plans or in these recommendations, the following compaction requirements are applicable to all electrical, gas or water conduits:

TABLE A COMPACTION DEPTH			
Area	Haunch to 1 ft. Above Top Of Pipe	1 ft. Above Top of Pipe to 2'6" Below Finished Grade	2'6" Below Finished Grade to Finished Subgrade
Structural	90%	90%	90%
Pavements	90%	90%	90%
Non-Structural	90%	90%	90%

D. ENGINEERED FILL

Earth materials obtained on site are acceptable for use as engineered fill provided that all grasses, weeds, and other deleterious debris are first removed. Engineered fill materials should be placed in thin layers (less than ten inches uncompacted thickness), brought to near the optimum moisture content or to a moisture content commensurate with effective compaction and soil stability, and compacted to a minimum of 90 percent of the maximum density obtainable by ASTM Test Method D1557, "Placing, Spreading and Compacting Fill Materials," in Appendix A.

E. IMPORTED FILL

The table shown below provides general guidelines for acceptance of import engineered fill. Materials of equal or better quality than on-site material could be reviewed by the Geotechnical Engineer on a case-by-case basis. No soil materials shall be imported onto the project site without prior approval by the Geotechnical Engineer. Any deviation from the specifications given below shall be approved by the Geotechnical Engineer prior to import operations.

MAXIMUM PERCENT PASSING #200 SIEVE	40
MAXIMUM PERCENT RETAINED 3" SIEVE.....	0
MAXIMUM PERCENT RETAINED 1½" SIEVE FOR BUILDING AREAS.....	15
MAXIMUM PERCENT RETAINED ¾" SIEVE FOR LANDSCAPE AREAS	5
MAXIMUM LIQUID LIMIT	40
MAXIMUM PLASTICITY INDEX.....	14
MINIMUM R-VALUE FOR PAVEMENT AREAS	50
MAXIMUM EXPANSION INDEX	20

Furthermore, the soils proposed for import shall be generally homogenous and shall not contain cemented or clayey and/or silty lumps larger than one inch. When such lumps are present, they shall not represent more than ten percent (10%) of the material by dry weight.

Where a proposed import source contains obviously variable soils, such as clay and/or silt layers, the soils which do not meet the above requirements shall be segregated and not used for this

project or the various layers shall be thoroughly mixed prior to acceptance testing by the Geotechnical Engineer.

The contractor shall provide sufficient advance notice, prior to import operations, to allow testing and evaluation of the proposed import materials. Because of the time needed to perform the above tests, the contractor shall provide a means by which the Geotechnical Engineer or others can verify that the soil(s) which was sampled and tested is the same soil(s) which is being imported to the project.

F. DRAINAGE

Finished ground grades adjacent to the proposed structures should be sloped to provide positive free drainage away from the foundations. No areas should be constructed that would allow drainage generated on the site, or water impinging upon the site from outside sources, to pond near footings and slabs or behind curbs.

Where ground surfaces adjacent to subsurface walls are to be landscaped, walls should be waterproofed. Installation of gravel-filled drains to route subsurface drainage away from walls will reduce the thickness of damp-proofing resulting in a considerable savings.

G. SLOPES

Both fill and cut slopes should be constructed at 2:1 (horizontal to vertical) in accordance with the 2022 California Building Code.

Finished slopes nearer than five feet from building foundations should be graded no steeper than five horizontal to one vertical (5:1). A slope ratio of two horizontal to one vertical (2:1) should provide adequate stability for slopes farther than five feet from footing lines.

The fill slopes shall be compacted to a minimum of 90% of ASTM D1557 and in accordance with the Guide Specifications for Earthwork, Appendix A. This may be achieved by overfilling the constructed slope and trimming to a compacted finished surface, rolling the slope face with a sheep'sfoot as the level of the fill is raised, or any method that achieves the desired product.

The cut portion of the slope should be constructed first. Prior to construction of the fill slope, incompetent surface soils should be removed from the top of the cut.

Areas to receive fill or to support structures, slabs or pavements should be removed of all vegetation, debris and disturbed soils. All existing uncertified fill soils should be excavated to expose competent native soils.

Existing underground pipelines, private sewage disposal systems and any water or oil wells, if encountered during grading, should be removed or capped in accordance with procedures considered acceptable by the appropriate governing agency. Tree roots to 2 inches in diameter should be removed.

Both fill and cut slopes will be subject to erosion immediately after grading, and should be designed to reduce surficial sloughing by implementing a permanent slope maintenance program as soon as practical after completion of slope construction.

Slope maintenance should include proper care of erosion and drainage control devices, rodent control, and immediate planting with deep-rooting, lightweight, drought-resistant vegetation. An erosion control geotextile may also be used in combination with vegetation to control erosion.

Experience has shown that slope performance is largely dependent upon proper slope maintenance (i.e., planting, proper watering, clearing of drainage devices, etc.). Slopes properly placed and conscientiously maintained are not expected to display excessive raveling or sloughing.

FOUNDATIONS RECOMMENDATIONS

The proposed structures could be supported on either spread footing or Cast-In-Place Drilled Piers. Following are both options:

Spread Footings – The proposed foundation could be supported on continuous spread footings in accordance with the following Table B:

TABLE B FOUNDATION DESIGN CRITERIA			
Footing Type	Minimum Width (ft.)	Minimum Depth Below Lowest Adjacent Subgrade (ft.)	Maximum Allowable Soil Bearing Pressure (lbs./sq.ft.)
Continuous	1	1.5	2500
Isolated	1	1.5	2500

Bearing pressures given are for the minimum widths and depths shown above.

Bearing pressures given above are for dead and sustained (loads acting most of the time) live loads; they may be increased by one-third for wind and/or seismic loading conditions.

The proposed foundations shall be reinforced in accordance with the structural engineer's recommendations.

Settlement:

Provided maximum allowable soil bearing pressures given above are not exceeded, total settlement should not exceed one inch. A major portion two-thirds to one-half of total settlement should occur before the end of construction. Differential settlements should occur before the end of construction. Differential settlements should, accordingly, be less than one-half of an inch for a horizontal span of twenty feet.

MODULUS OF SUBGRADE REACTION

Modulus of subgrade reaction for use in design of foundations is based on ranges of values for soil types provided by Foundation Analysis and Design by Joseph E Bowles.¹ Equation 1 should be used for footings on sandy soils.

Foundations on clay soils should employ Equation 2. Equation 3 is for rectangular footings having dimensions $w = b$ (width) and $l = mb$ (length) the variable "m" being the ratio of the length to the width of the foundation. K_{s1} is the modulus of subgrade reaction from the source referenced above based on a 1 foot x 1 foot square plate. For general guidance K_{s1} of 150 kcf may be used for the subsurface sandy soils.

$$\text{Equation (1)} \quad k_{sf} = K_{s1} \times \left(\frac{B+1}{2B} \right)^2$$

$$\text{Equation (2)} \quad k_{sf} = K_{s1} \times B$$

$$\text{Equation (3)} \quad k_{sf} = K_{s1} \times \frac{m+5}{1.5 \times m}$$

Values given above should be used for guidance. Local values may be higher or lower and should be based on results of in-situ plate bearing tests performed in accordance with ASTM Test Method D1194.

LATERAL EARTH PRESSURES

Lateral earth pressures and friction coefficients for determining the passive lateral resistance of foundations against lateral movement and the active lateral forces against retaining walls and subsurface walls, expressed as equivalent fluid pressures, are given below in Table C. Lateral earth pressures were computed assuming that backfill materials are essentially free draining and level; and that no surcharge loads or sloping backfills are present within a distance from the wall equal to or less than the height (H)* of the wall.

(H)* = the height of backfill above the lowest adjacent ground surface.

TABLE C LATERAL EARTH PRESSURES	
Case	Lateral Earth Pressures
Active	40 P.C.F.
Passive	390 P.C.F.
At-Rest	50 P.C.F.

Active Case: Active lateral earth pressures should be used when computing forces against free standing retaining walls, unrestrained at the tops. Active pressures should not be used where tilting outward of the walls is greater than .002H would not be desirable.

¹ Bowles, Joseph E; FOUNDATION ANALYSIS AND DESIGN; McGraw-Hill Book Company (1977); Table 9-1 pg 269

Passive Case: Passive lateral earth pressures should be used when computing the lateral resistance provided by undisturbed or compacted native soils against the movement of footing. When computing passive resistance, the upper one foot of embedment depth should be discounted.

At-Rest Case: At-rest pressures should be used for subsurface walls restrained at their tops by floor diaphragms or tie-backs and for retaining walls where tilting outward greater than .002 H would not be desirable.

Frictional Resistance: A friction coefficient of **0.42** may be used when computing the frictional resistance to sliding of footings, grade beams, and slabs-on-grade. Frictional resistance and passive lateral soil resistance may be combined without reduction.

SOIL CORROSIVITY

Soluble Sulfates (SO₄)

The highest Sulfate (SO₄) concentration measured was 98 ppm.

Based on Table 19.3.1.1 "Exposure categories and classes" of ACI 318-14 "Building Code Requirements for Structural Concrete" the soil exposure is classified as S0. Per Table 19.3.2.1 "Requirement for Concrete by Exposure Class" of the same reference, no restriction applies to the cement type or mix design.

Chlorides (Cl)

The highest Chloride (Cl) concentration measured was 14 ppm. Generally, chloride concentrations greater than 500 ppm are considered to be corrosive to foundation elements. (Ref: Caltrans Corrosion Guidelines / Version 1.0)

pH

The soil pH result was measured at 8.29. Generally, a pH level less than 5.5 are considered to be corrosive to foundation elements. (Ref: Caltrans Corrosion Guidelines / Version 1.0)

Although preliminary test results indicate that soil corrosivity at the locations and depths tested is low to negligible, if the site grading operations will result in a blend of native and/or imported materials at finished subgrade elevations, additional tests should be performed after rough grading has been completed and prior to concrete and/or mechanical design.

The authors of this report, Soils Engineering, Inc., are not experts in the field of soil corrosivity. Should detailed analysis of soil corrosivity be required, it is our recommendation to contract a corrosion engineer.

SLABS-ON-GROUND

Slabs-on-ground may be supported on earth materials prepared in accordance with the recommendations of this Geotechnical Investigation.

Moisture protection between the soil and the interior slabs-on-ground is recommended. For exceptions to slab moisture protection, refer to the 2022 California Building Code, §1907.1. The project designer should provide specific details regarding construction of the concrete slab-on-ground, including the moisture barrier or vapor retarder/barrier, capillary break (if included), and blotter material (if included). The American Concrete Institute recommends a minimum moisture vapor retarder of 10 mil thick polyethylene. The vapor retarder should be protected from damage. Punctures and tears should be repaired prior to concrete placement. It is our opinion that existing soil and groundwater conditions do not warrant the inclusion of a capillary break.

It has been common local practice to use a sandy material as a blotter layer between the moisture barrier and the concrete to absorb some of the bleed water and to potentially reduce slab curling. However, a blotter layer may act as a moisture reservoir. If that occurs, all apparent advantages of its use are negated. A blotter layer should not be incorporated into the section design for moisture-sensitive slabs if it cannot be kept dry prior to concrete placement or if water may migrate into the layer after slab construction (eg. wet curing, rainfall). If the slab-on-ground section is to include a blotter layer between the moisture barrier and the concrete, it is our recommendation that the blotter material consist of crusher fines (rock dust) or sand with angular, interlocking grains. The material should be easily compacted and should be screened so that 100% of the material is finer than 1/4". Do not use blotter material which may be potentially reactive with the alkalis in the concrete or which has high sulfate content. At the time of concrete placement, the blotter material should be dry to damp, compact, and smooth. For slabs which are to be water-cured, a blotter layer should not be used. For further consideration, refer to the American Concrete Institute *Manual of Concrete Practice 302.1R and 360*.

Slab thicknesses, reinforcing, and the concrete characteristics should be in accordance with the project designer's recommendations. The 2022 California Building Code, §1907.1 requires that the slab thickness be not less than 3½".

Pressurized water lines should not be installed beneath slabs-on-ground. Where pressurized water lines must be routed beneath the slab, they should be routed entirely inside continuous sleeves with both ends open to the atmosphere above the slab surface. Gravity flow sewer lines may underlie slabs-on-ground, but they should be routed to the exterior point of connection by the shortest feasible path.

PAVEMENT FIELD INVESTIGATION & DESIGN DATA

Three (3) borings were drilled to a maximum depth of five (5) feet below existing grade. Bore locations are shown on the attached Boring Location Map, Figure 1.

Hot Mix Asphalt (HMA) pavement shall be designed based on the lowest Resistant (R) Value test result of R=30. The laboratory test reports are provided as Figures D-1 through D-3.

HMA design should meet the requirements of the 2010 or newer, State of California, Standard Specifications Manual (SSM), Section 39. Aggregate Base should also meet the Class 2 requirements of the SSM, Section 26.

PCC design should meet the requirements of the American Concrete Institute (ACI) 330R, Guide for the Design and Construction of Concrete.

Ground surfaces to receive HMA or Portland Cement Concrete (PCC) pavements should be scarified and compacted to a minimum depth of 12 inches below the grading plane in cut areas or to 12 inches in areas to receive fill. Engineered fill placed in proposed pavement areas should conform to the requirements of section 5.4, "Placing, Spreading and Compacting Fill Materials," of Appendix A.

Compaction in proposed pavement areas should be a minimum of 90 percent of the maximum density as obtained to ASTM Test Method D1557 and 95% in the upper 8 inches, and should extend to a minimum of two feet beyond the outside edges of pavements.

These recommendations are valid only if the pavement is properly drained and shoulder areas are graded to prevent water ponding at pavement edges. All construction should be subject to adequate tests and observations to verify conformance with these recommendations.

LIMITATIONS, OBSERVATION AND TESTING

Conclusions and recommendations in this report are given for the New District Office and MOT Yard, located at 6327 Zephyr Lane, Bakersfield, California and are based on the following:

- a. The information retrieved from five (5) exploratory borings drilled at the subject site to a maximum depth of 21.5 feet below the existing ground surface.
- b. Our laboratory testing program results.
- c. Our engineering analysis based on the information defined in this report.
- d. Our experience in the Kern County area.

Variations in soil type, strength and consistency may exist between specific boring locations. These variations may not become evident until after the start of construction. If such variations appear, a re-evaluation of the soils test data and recommendations may be necessary.

Unless a Geotechnical Engineer of this firm is afforded the opportunity to review plans and specifications, we accept no responsibility for compliance with design concepts or interpretations made by others with regard to foundation support, fill selection, fill placement or other recommendations presented in this report.

Changes in conditions of the subject property can occur with time because of natural processes or the works of man on the subject site or on adjacent properties. Changes in applicable engineering and construction standards can also occur as the result of legislation or from the broadening of knowledge.

Accordingly, the finding of this report may be invalidated, wholly or in part, by changes beyond our control. Therefore, this report is subject to review and should not be relied upon without review after a period of two years or after any modifications to the site.

REVIEW OF EARTHWORK OPERATIONS

Review of earthwork operations relating to site clearing, ground stabilization, placement and compaction of fill materials, and finished grading is critical to the structural integrity of building foundation and floor systems.

While the preliminary Geotechnical investigation and report provide guidelines which are used by the design team, i.e., architects, grading engineers, structural engineers, landscape engineers, etc., in completing their respective tasks, review of plans and site review and testing during earthwork operations are vital adjuncts to the completion of the Geotechnical engineer's tasks.

The most prevalent cause of failure of a structure foundation system is lack of adequate review and testing during the earthwork phase of the project. Projects rarely reach completion without some alteration being required such as may result from a change in subsurface conditions, an amendment in the size and scope of the project, a revision of the grading plans or a variation in structural details. Occasionally, even minor changes can significantly affect the performance of foundations.

The most prevalent secondary cause for foundation failure is inadequate implementation of Geotechnical recommendations during the formulation of foundation designs and grading plans. The error in a foundation design or an omission of a key element from a grading plan occurs most often as a result of inadequate communication between the various project consultants and -- when a change in consultants occurs -- improper transfer of authority and responsibility².

It is imperative, therefore, that any revisions to the project scope, any change in structural detail, or change in consultant, be brought to the attention of Soils Engineering, Inc. to allow for timely review and revision of recommendations and for an orderly transfer of responsibility and approval.

It is the responsibility of the owner or his or her representative to ensure that a representative of our firm is present at all times during earthwork operations relating to site preparation and grading, so that relative compaction tests can be performed, earthwork operations can be observed and compliance with the recommendations provided herein can be established.

This engineering report has been prepared within the limits prescribed to us by the client or his or her representative, in accordance with the generally accepted principles and practices of Geotechnical engineering. No other warranty, expressed or implied, is included or intended in this report.

Respectfully submitted,
SOILS ENGINEERING, INC.

² If the civil engineer, the soils engineer, the engineering geologist or the testing agency of record is changed during the course of the work, the work shall be stopped until the replacement has agreed to accept the responsibility within the area of his or her technical competence for approval upon completion of the work.

APPENDIX A

GENERAL GUIDE SPECIFICATIONS FOR EARTHWORK

1. GENERAL

1.1 Scope

These specifications and plans include all earthwork pertaining to site rough grading including, but not limited to furnishing all labor and equipment necessary for clearing and grubbing; stripping; preparation of ground surfaces to receive fill; excavation; placement and compaction of structural and non-structural fill; disposal of excess materials and products of clearing, grubbing, and stripping; and any other work necessary to bring ground elevations to the lines and grades shown on the project plans.

1.2 Performance:

It shall be the responsibility of the contractor to complete all earthwork in accordance with project plans and specifications. No variance from plans and specifications shall be permitted without written approval of the Engineer-of-Record, hereinafter referred to as the "engineer" or his or her designated representative, hereinafter referred to as the "soils engineer." Earthwork shall not be considered complete until the "engineer" has issued a written statement confirming substantial compliance of earthwork operations to these specifications and to the project plans.

The contractor shall assume sole responsibility for job site conditions during the course of earthwork operations on the project, including safety of all persons and preservation of all property; this requirement shall apply continuously and not be limited to normal working hours. The contractor shall defend, indemnify, and hold harmless the owners, engineer, and soils engineer from any and all liability and claims, real or alleged, arising out of performance of earthwork on this project, except from liability incurred through sole negligence of the owner, engineers, or soils engineers.

2. DEFINITIONS

2.1 Excavations:

Excavation shall be defined within the content of these specifications as earth material excavated for the purpose of constructing fill embankment; grading the site to elevations shown on project plans; or placing underground pipelines, conduits, or other subsurface utilities or minor structures.

Excavations shall be made true to the lines shown on project plans and to within plus or minus one-tenth (0.1) of a foot, of grades shown on the accepted site grading plans.

2.2 Engineered Fill:

Engineered fill shall be construed within the body of these specifications as earth materials conforming to specifications provided in the soils or geotechnical report placed to raise the grade of the site, to backfill excavations, or to construct asphaltic concrete or Portland cement concrete pavement; and upon which the soils engineer has performed sufficient tests and has made sufficient observation during placement and compaction to enable him to issue a written statement confirming substantial conformance of the work to project earthwork specifications.

2.3 On-Site Material:

On-site material is earth material obtained in excavation made on the project site.

2.4 Imported Material:

Imported materials are earth materials obtained off the site, hauled in, and placed as fill.

2.5 “Compaction” or “Compacted:”

Wherever expressed or implied within the context of these specifications shall be interpreted as compaction to ninety (90) percent of the maximum density obtainable by ASTM Test Method D1557.

2.6 Grading Plane:

The grading Plane is the surface of the basement material upon which the lowest layer of subbase, base, asphaltic or Portland cement concrete, surfacing, or other specified layer is placed.

3. SITE CONDITIONS

The contractor shall visit the site, prior to bid submittal, to determine existing soil and topographic conditions, and the nature of materials that may be encountered during the course of the work under this contract and make his or her own interpretation of the contents of the Geotechnical Report, as they pertain to said conditions.

The contractor shall assume all liability under the contract for any loss sustained as a result of variations which may exist between specific soil boring locations or changed conditions resulting from natural or man-made circumstances occurring after the date of the Preliminary Field Investigations.

4. CLEARING AND GRUBBING

4.1 Clearing and Grubbing

Clearing and grubbing shall consist of removing all debris such as metal, broken concrete, trash, vegetation growth and other biodegradable substances, from all areas to be graded. Existing obstructions below shall be removed in accordance with the following procedures:

- 4.1.1 Slabs and Pavements** – Shall be completely removed. Asphaltic or Portland Cement, concrete fragments may be used in engineered fills provided they are broken down to a maximum dimension of six (6.0) inches and thoroughly dispersed within a friable soil matrix. Engineered fill containing said fragments should not be placed above the elevation of the bottom of the lowest structure footing.
- 4.1.2 Foundations** – existing at the time of grading shall be removed to a depth not less than two (2.0) feet below the bottom of the lowest structure footing.
- 4.1.3 Basements, Septic Tanks** – buried concrete containers of similar construction located within areas destined to receive pavements, structures, or engineered fills should be completely removed and disposed of off the site. Basements, septic tanks, etc., situated outside structures, or structural fill areas shall be disposed of by breaking an opening in bottoms to permit drainage, and by breaking walls down to not less than two (2.0) feet below finished subgrade.
- 4.1.4 Buried Utilities** – such as sewer, water and gas lines or electrical conduits to remain in service shall be re-routed to pass no closer than four (4.0) feet to the outside edge of proposed exterior footings of structures. Lines to be abandoned shall be completely removed to a minimum depth of two (2.0) feet below finished building pad grade. Concrete lines deeper than two (2.0) feet below finished building pad grade and having diameters less than six (6.0) inches can be crushed in place.
- 4.1.5 Root Systems** – shall be completely removed to a minimum depth of two (2.0) feet below the bottom of the lowest proposed structure footing or to two (2.0) feet below finished subgrade, whichever depth is lower. Root systems deeper than the elevation indicated above shall be excavated to allow no roots larger than two (2.0) inches in diameter.
- 4.1.6 Cavities** – resulting from clearing and grubbing or cavities existing on the site as a result of man-made or natural activity shall be backfilled with earth materials placed and compacted in accordance with Sections 5.3 and 5.4 of these specifications.

- 4.1.7 Preservation or Monuments, Construction Stakes, Property Corner Stakes**, or other temporary or permanent horizontal or vertical control reference points shall be the responsibility of the contractor. Where these markers are disturbed, they shall be replaced at the contractor's expense.

5. SITE GRADING

Site grading shall consist of excavation and placement of fills to lines and grades shown on the project plans and in accordance with project specifications and recommendations of the Preliminary Soils Report, whichever is more stringent. The following are recommendations issued in this report.

5.1 Areas to Receive Fill:

- 5.1.1** Surfaces to receive fill shall be scarified to a depth of at least six (6.0) inches, or as recommended in this report, whichever is greater, until the surface is free from ruts, hummocks or other uneven features which would tend to prevent uniform compaction by the equipment to be used.
- 5.1.2** After the area to receive fill has been cleared and scarified, it shall be moistened and compacted to a depth of at least six (6.0) inches in accordance with specifications for compacting fill material in paragraph 5.4, below.

5.2 Excavation:

- 5.2.1** Excavations shall be cut to elevations plus or minus 0.1 foot of the grades shown on the accepted plans.
- 5.2.2** When excavated materials are to be used in engineered fill, the excavation shall be made in a manner to produce as much mixing of the excavated materials as practicable.
- 5.2.3** When excavations are to backfilled, and where surfaces exposed by excavation are to support structures or concrete floor slabs, the exposed surfaces shall be scarified, moistened and compacted, as stated above for areas to receive fill. Over excavation below specified depths will not eliminate the requirement for exposed surface compaction.

5.3 Fill Materials:

- 5.3.1** Materials obtained from on-site excavations will be considered satisfactory for construction of on-site engineered fills unless otherwise stated in the Soils Report or Foundation Investigation.

If unexpected pockets of poor or weak materials are encountered in excavations, and they cannot be upgraded by mixing with other materials

or by other means, they may be rejected by the soils engineer for use in engineered fill.

Rocks larger than 12 inches in size in any dimension shall not be allowed in the proposed building area. If a large amount of rocks greater than 12 inches in size in any dimension is encountered a rock disposal area shall be located on the grading plan. Rocks shall be mixed with well graded soils to assure that the voids in these areas will fill properly.

5.3.2 When imported fill materials are necessary to bring the site up to planned grades, no material shall be imported prior to its approval and acceptance by the soils engineer.

5.3.3 The soils engineer shall be given notice of the proposed source of imported materials with adequate time allowance for his or her testing of the proposed materials. The time required for testing will vary with different types of materials, job conditions, and ultimate function of filled areas. Under best conditions the time requirement will not be less than 48 hours.

5.4 Placing, Spreading, and Compacting Fill Material:

5.4.1 The fill materials shall be placed in layers which, when compacted, shall not exceed six (6.0) inches in thickness. Each layer shall be spread evenly and shall be thoroughly mixed during the spreading to insure uniformity of material in each layer. Increased thickness of layers may be approved by the soils engineer when conditions warrant.

5.4.2 All fills shall be placed in level layers; layers shall be continuous over the area of any structural unit, and all portions of the fill shall be brought up simultaneously within the area of any structural unit. When imported material is used, it must be placed so that its thickness is as uniform as possible within the area of any structural unit.

5.4.3 When materials are to be excavated and replaced in a compacted condition, segmented, or leap-frogging of cut-fill operation within the area of any structural unit will not be permitted unless the method is specifically described by the soils engineer.

5.4.4 When the moisture content of fill material is below the lower limit specified by the Soils Engineer, water shall be added until the moisture content is as specified; and when it is above the upper limit specified, the material shall be aerated by blading or other satisfactory methods until the moisture content is as specified.

5.4.5 After each layer has been placed, mixed, and spread evenly, it shall be thoroughly compacted to not less than ninety (90) percent of maximum density in accordance with ASTM Density Test Method D1557. Compaction shall be by equipment of such design that it will be able to

compact the fill to specified density. When the soils engineer specifies a specific type of compaction equipment to be used, such equipment shall be used as specified.

- 5.4.6** Compaction of each layer shall be continuous over its entire area and the equipment shall make sufficient trips to ensure that the desired density has been obtained.
- 5.4.7** Field density tests shall be made by the soils engineer. The compaction of each layer of fill shall be subject to testing. Where sheepsfoot rollers are used, the soil may be disturbed to a depth of several inches. Density tests shall be taken in the compacted material below the disturbed surface. When tests indicate the density of any layer of fill or portion thereof is below the required ninety (90) percent density, the particular layer or portion shall be re-worked until the required density has been obtained.
- 5.4.8** When the soils engineer specifies compaction to other standards or to percentages other than ninety (90) percent, such specification, with respect to the particular items shall supersede these specifications.
- 5.4.9** The fill operation shall be continued in six (6) inch compacted layers, as specified above, until the fill has been brought to within 0.1 foot, plus or minus of the finished slopes and grades, as shown on the accepted plans. The finished surface of fill areas shall be graded or bladed to a smooth and uniform surface and no loose material shall be left on the surface.
- 5.4.10** No fill materials shall be placed, spread, or compacted while it is frozen or thawing or during unfavorable weather conditions. When work is interrupted by weather conditions, fill operations shall not be resumed until the soils engineer indicates that moisture content and density of previously placed fill are satisfactory.

5.5 Observations and Testing:

The soils engineer shall be provided with a 48 hour advance notice, in order that he may be present at the site during all earthwork activities related to excavation, tree root removal, stripping, backfill, and compaction and filling of the site and to perform periodic compaction tests so that substantial conformance to these recommendations can be established.

APPENDIX B

FIELD INVESTIGATION

Five (5) test borings were drilled at the subject site and terminated at a maximum depth of 21.5 feet below the existing ground surface. Borings were advanced using an (4.25) inch hollow-stem auger. Test data and descriptions from these holes form the basis of the conclusions and recommendations contained in this report.

Undisturbed samples and disturbed bulk samples were obtained. Undisturbed samples were taken using either a 2-3/8" (inside diameter) split-barrel sampler or a 1-3/8" (inside diameter), 2" (outside diameter) Standard Penetration Sampler (SPT). Penetration resistance of undisturbed soils was obtained by driving the above-described sampler using a one-hundred-forty-pound hammer falling thirty inches (30"). Blow counts for each six inch (6") driven increment was recorded and are reported on the Test Borings Logs. In addition, bulk soil samples, selected as most representative of near surface soils encountered, were taken for laboratory testing.

As drilling progressed, earth materials encountered were logged and classified in accordance with the Unified Soils Classification System and presented graphically on Logs of Test Borings, Figures 2 through 6, along with the Legend. Approximate locations of test borings are shown on the Boring Location Map, Figure 1.



NEW DISTRICT OFFICE AND MOT

SITE PLAN SCHEME 2

PARKING REQUIREMENTS

BUSINESS/OFFICE: 1 PER 250 SF
WAREHOUSE: 1 PER 1,000 SF


1 TREE PER 6 PARKING SPACES
(65FT SPACING MAX)

WORST CASE PARKING
REQUIRED:

28 PARKING STALLS FOR MOT
54 PARKING STALLS FOR DO

PROVIDING **205** PARKING STALLS

Legend




Boring Location Map Figure 1 SEI File No. 23-19257



9/13/2023

ZEPHYR LANE





LOG OF TEST BORING BORING B-1

Page 1 of 1

PROJECT: *New District Office and MOT Yard*
BORING DATE: *10/16/23*
BORING LOCATION: *See Boring Location Map, Figure 1*
DRILL METHOD: *4.25" I.D. Hollow-Stem Auger*
DESCRIPTION: *Geotechnical Engineering Services*
DEPTH TO WATER -  : *N/A*

FILE NO: *19257*
ELEV.: *Approx. 400'*
START: *10/16/23*
FINISH: *10/16/23*

CAVING -  : *N/A*

LOGGER: *LW*

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Description	Remarks	Density pcf	Moisture %
0		CL	SANDY CLAY; light brown, dry to damp, medium plasticity.			
8/6 16/6 24/6			Very stiff.		95.1	9.7
5						
8/6 10/6 14/6					93.7	11.1
10						
7/6 11/6 16/6					113.4	11.9
15		SP	POORLY GRADED SAND; olive brown, damp to moist, fine grained.		103.6	16.6
7/6 15/6 17/6		CL	Medium dense. SANDY CLAY; brown, moist, medium plasticity.			
20			Very stiff.		110.3	17.7
5/6 10/6 19/6			BOTTOM.			
25						
30						
35						

Figure Number 2



LOG OF TEST BORING BORING B-2

Page 1 of 1

PROJECT: *New District Office and MOT Yard*
BORING DATE: *10/16/23*
BORING LOCATION: *See Boring Location Map, Figure 1*
DRILL METHOD: *4.25" I.D. Hollow-Stem Auger*
DESCRIPTION: *Geotechnical Engineering Services*
DEPTH TO WATER - ∇ : *N/A*

FILE NO: *19257*
ELEV.: *Approx. 400'*
START: *10/16/23*
FINISH: *10/16/23*

CAVING - $\blacktriangleright$: *N/A*

LOGGER: *LW*

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Description	Remarks	Density pcf	Moisture %
0		SM	SILTY SAND; brown, damp, fine, cohesive.			
7/6 8/6 8/6			Medium dense.		100.6	7.4
5		ML	SANDY SILT; brown, damp, medium plasticity.			
7/6 26/6 28/6			Hard.		98.7	9.6
10						
8/6 13/6 17/6			Very stiff.		109.4	12.3
15		CL	CLAY; olive brown, moist, medium plasticity.			
7/6 11/6 11/6			Stiff.		108.9	15.2
20						
5/6 13/6 16/6			Very stiff. BOTTOM.		100.7	22.7
25						
30						
35						

Figure Number 3



LOG OF TEST BORING BORING B-3

Page 1 of 1

PROJECT: *New District Office and MOT Yard*
BORING DATE: *10/16/23*
BORING LOCATION: *See Boring Location Map, Figure 1*
DRILL METHOD: *4.25" I.D. Hollow-Stem Auger*
DESCRIPTION: *Geotechnical Engineering Services*
DEPTH TO WATER - : *N/A* **CAVING -** : *N/A*

FILE NO: *19257*
ELEV.: *Approx. 400'*
START: *10/16/23*
FINISH: *10/16/23*

LOGGER: *LW*

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Description	Remarks	Density pcf	Moisture %
0		SC	CLAYEY SAND; light brown, dry to damp, fine, cohesive.			
	7/6 17/6 14/6		Medium dense.		109.2	6.5
5		CL	SANDY CLAY; pale brown, damp, medium plasticity. Hard.		108.0	14.3
	9/6 34/6 46/6					
10			Light brown, stiff.		103.1	10.3
	6/6 10/6 12/6	CL	CLAY; olive brown, moist, medium plasticity.			
15					107.9	17.1
	5/6 10/6 13/6					
20			Very stiff. BOTTOM.		99.7	24.1
	5/6 10/6 18/6					
25						
30						
35						

Figure Number 4



LOG OF TEST BORING BORING B-4

Page 1 of 1

PROJECT: *New District Office and MOT Yard*
BORING DATE: *10/16/23*
BORING LOCATION: *See Boring Location Map, Figure 1*
DRILL METHOD: *4.25" I.D. Hollow-Stem Auger*
DESCRIPTION: *Geotechnical Engineering Services*
DEPTH TO WATER - : *N/A* **CAVING -** : *N/A*

FILE NO: *19257*
ELEV.: Approx. *400'*
START: *10/16/23*
FINISH: *10/16/23*

LOGGER: *LW*





ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Description	Remarks	Density pcf	Moisture %
0		SC	CLAYEY SAND; light brown, damp, fine, cohesive.			
10/6 10/6 9/6			Medium dense.		100.9	4.8
5		ML	SANDY SILT; light brown, damp, medium plasticity. Stiff.		88.4	8.9
4/6 7/6 15/6			Very stiff.		108.4	14.6
10						
10/6 16/6 17/6						
15						
5/6 9/6 15/6					97.3	16.9
20						
6/6 13/6 20/6			BOTTOM.		107.4	17.8
25						
30						
35						

Figure Number 5



LOG OF TEST BORING

BORING B-5

Page 1 of 1

PROJECT: *New District Office and MOT Yard*

BORING DATE: *10/16/23*

BORING LOCATION: *See Boring Location Map, Figure 1*

DRILL METHOD: *4.25" I.D. Hollow-Stem Auger*

DESCRIPTION: *Geotechnical Engineering Services*

DEPTH TO WATER - : *N/A*

CAVING - : *N/A*

FILE NO: *19257*

ELEV.: Approx. *400'*

START: *10/16/23*

FINISH: *10/16/23*

LOGGER: *LW*

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Description	Remarks	Density pcf	Moisture %
0		SC	CLAYEY SAND; light brown, damp, fine, cohesive. Medium dense.			
11/6 13/6 11/6					104.1	6.9
5						
7/6 19/6 28/6			Dense.		88.3	13.4
10		CL	CLAY; olive brown, damp to moist, medium plasticity. Stiff.			
5/6 9/6 11/6					94.3	16.2
15						
4/6 9/6 12/6					111.7	21.7
20						
5/6 10/6 14/6			Very stiff. BOTTOM.		106.5	19.6
25						
30						
35						

Figure Number 6

KEY TO SYMBOLS

Symbol Description

Strata symbols



**Low plasticity
clay**



Poorly graded sand



Silty sand



Silt



Clayey sand

Soil Samplers



California sampler

Notes:

1. Five (5) exploratory borings were drilled on 10/16/2023 using an 8-inch outside diameter hollow-stem auger.
2. No free groundwater was encountered to the maximum depth drilled of 21.5'.
3. Boring locations are shown on the Boring Location Map, Figure 1.
4. These logs are subject to the limitations, conclusions, and recommendations in this report.
5. Results of tests conducted on samples recovered are reported on the logs.

APPENDIX C**SOIL TEST DATA****SIEVE ANALYSES (ASTM D422 and/or ASTM D1140)**

Grain size distributions for specimens retrieved from various subsurface elevations were tested to classify the materials. Test results are presented on Figures A-1 and A-2.

IN-SITU DENSITY & MOISTURE RELATIONSHIPS (ASTM D2216 & D2937)

Moisture & density data for undisturbed native soils was obtained by use of a 2-3/8-inch (inside diameter) split-barrel sampler. Test results are given on the Logs of Test Borings, Figures 2 through 6.

CONSOLIDATION TESTS (ASTM D2435)

Compressibility of soils was determined on saturated, undisturbed samples of native materials. Consolidation Test Diagrams, Figures B-1 and B-2, graphically express the relationship of vertical strain vs. applied vertical (normal) load for earth materials selected as most representative of the soil strata within the anticipated zone of influence of foundation loads.

DIRECT SHEAR TESTS (ASTM D3080)

A quick-consolidated direct shear test was performed on an undisturbed, saturated sample of native earth materials. This test provides information on soil shear strength vs. normal load and is used to determine the angle of internal friction and cohesion of earth materials under essentially drained conditions. Test results are presented on Figures C-1 and C-2.

EXPANSION INDEX (ASTM D4829)

The Expansion Index test is designed to measure a basic index property of soil and in this respect is comparable to other index tests such as the Atterberg Limits. In formulating the test procedures, no attempt has been made to duplicate any particular moisture or loading conditions which may occur in the field. Rather, an attempt has been made to control all variables which influence the expansive characteristics of a particular soil and still retain a practical test for general engineering usage. Near surface soils were obtained and tested for expansiveness. Test results are presented on the Laboratory Testing Recap Table 1.

R-VALUE TESTS (CTM-301)

R-Value tests were performed to obtain flexible pavement design data. Test results are presented on Figures D-1 through D-3.

SOIL CORROSIVITY (SO₄ / pH / Chlorides)

Tests for Soluble Sulfates (SO₄), Soluble Chlorides (Cl), and pH values were performed on one (1) composite sample taken from the upper 5 feet to determine the corrosion potential of the soils. Corrosion prevention measures and the extent to which measures should be taken (if any) should be addressed with the corrosion engineer. Soluble Sulfates and Soluble Chlorides values were determined according to EPA 300.0M. The pH values were determined according to EPA 9045C. Results of all the constituent(s) are discussed in the Soil Corrosivity section.

TABLE 1

TEST LOCATION	USCS	% < # 200	CONSOLIDATION				DIRECT SHEAR		UNCONFINED COMPRESSION		E.I.	MINIMUM RESISITIVITY	ATTERBERG LIMITS			R-VALUE @ 300 psi		MAXIMUM DENSITY	
			C _c	C _s	S.P. (psf)	HV %	C, (ksf)	F.A.	Q _u , (psi)	C, (ksf)			LL	PL	PI	R.V.	E.P. (psi)	MDD (pcf)	O.M.
B-2 @ 3'	SM	49					0.12	31.7											
B-2 @ 6'	ML	80	0.14	0.01	0	-3.1													
B-4 @ 0-5'	SM	49									5								
B-4 @ 3'	SC						0.12	31.3											
B-4 @ 6'	ML	64	0.24	0.01	0	-4.7													
R-1 @ 0-5'	SM	36														69	0		
R-2 @ 0-5'	ML	67														30	0.04		
R-3 @ 0-5'	ML	50														35	0.11		

CONSOLIDATION
Cc - Compression Index
Cs - Swell Index
S.P. (psf) - Swell Pressure
HV % - Heave Precentage / Collapase

UNCONFINED COMPRESSION
Q_u (psi) - Unconfined Compression
Strength
C, (ksf) - Cohesion


DIRECT SHEAR
C (ksf) - Cohesion
F.A. - Friction Angle

E.I. - EXPANSION INDEX
ATTERBERG LIMITS
LL - Liquid Limit
PL - Plastic Limit
PI - Plasticity Index

RESISTANCE VALUE (R-VALUE)
RV - R-Value @ 300 psi
EP - Expansion Press @ 300 psi
MINIMUM RESISITIVITY - (ohm-cm)

MAXIMUM DENSITY
MDD (pcf) - Max Dry Density
O.M. - Optimum Moisture

Particle Size Distribution Report



	% +3"	% Gravel		% Sand			% Fines	
		Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
○							49	
□							80	
△							49	
◇							64	
▽							36	

SOIL DATA					
SYMBOL	SOURCE	SAMPLE NO.	DEPTH (ft.)	Material Description	USCS
○	B-2		3'	SILTY SAND	SM
□	B-2		6'	SANDY SILT	ML
△		91059	0-5'	SILTY SAND (B-4)	SM
◇	B-4		6'	SANDY SILT	ML
▽		91070	0-5'	SILTY SAND (R-1)	SM


SOILS ENGINEERING, INC.

Client: Fairfax School District
Project: New District Office and MOT Yard
Project No.: 19257

Figure A-1

Tested By: ○ RC □ SC △ DH ◇ SC

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
○						67	
□						50	


SOIL DATA					
SYMBOL	SOURCE	SAMPLE NO.	DEPTH (ft.)	Material Description	USCS
○		91071	0-5'	CLAYEY SILT (R-2)	ML
□		91072	0-5'	SANDY SILT (R-3)	ML

SOILS ENGINEERING, INC.

Client: Fairfax School District
Project: New District Office and MOT Yard
Project No.: 19257

Figure A-2

CONSOLIDATION TEST REPORT



Natural		Dry Dens. (pcf)	LL	PI	Sp. Gr.	Overburden (psf)	P_c (psf)	C_c	C_s	Swell Press. (psf)	Heave %	e_o
Sat.	Moist.											
34.4 %	11.7 %	87.0	N/A	N/A	2.65	336	2658	0.14	0.01		-3.1	0.902

MATERIAL DESCRIPTION										USCS	AASHTO
SANDY SILT										ML	N/A

Project No. 19257 **Client:** Fairfax School District

Project: New District Office and MOT Yard

Source of Sample: B-2 **Depth:** 6'

Remarks:

Test Date: 11/8/23
Sample No: 91050

SOILS ENGINEERING, INC.

Figure B-1

Tested By: SC





Dial Reading vs. Time

Project No.: 19257

Project: New District Office and MOT Yard

Source of Sample: B-2


Depth: 6'



SOILS ENGINEERING, INC.

Figure B-1

CONSOLIDATION TEST REPORT



Natural		Dry Dens. (pcf)	LL	PI	Sp. Gr.	Overburden (psf)	P_c (psf)	C_c	C_s	Swell Press. (psf)	Heave %	e_o
Sat.	Moist.											
22.3 %	11.3 %	70.8	N/A	N/A	2.65	336	2623	0.24	0.01		-4.7	1.337

MATERIAL DESCRIPTION										USCS	AASHTO
SANDY SILT										ML	N/A

Project No. 19257		Client: Fairfax School District		Remarks: Test Date: 11/8/23 Sample No: 91061
Project: New District Office and MOT Yard				
Source of Sample: B-4		Depth: 6'		
SOILS ENGINEERING, INC.				

Figure B-2

Figure B-2

Tested By: SC





Dial Reading vs. Time

Project No.: 19257

Project: New District Office and MOT Yard

Source of Sample: B-4

Depth: 6'



SOILS ENGINEERING, INC.


Figure B-2

Dial Reading vs. Time

Project No.: 19257




Project: New District Office and MOT Yard

Source of Sample: B-4 Depth: 6'



SOILS ENGINEERING, INC.

Figure B-2



Sample No.		1	2	3
Initial	Water Content, %	10.8	7.1	9.8
	Dry Density, pcf	90.9	93.0	93.3
	Saturation, %	34.9	24.2	33.5
	Void Ratio	0.8201	0.7797	0.7731
	Diameter, in.	2.38	2.38	2.38
	Height, in.	1.00	1.00	1.00
At Test	Water Content, %	25.8	24.1	23.6
	Dry Density, pcf	90.9	93.0	93.3
	Saturation, %	83.5	81.7	80.9
	Void Ratio	0.8201	0.7797	0.7731
	Diameter, in.	2.38	2.38	2.38
	Height, in.	1.00	1.00	1.00
Normal Stress, ksf		1.00	2.00	4.00
Fail. Stress, ksf		0.74	1.36	2.59
Displacement, in.		0.12	0.21	0.24
Ult. Stress, ksf				
Displacement, in.				
Strain rate, in./min.		N/A	N/A	N/A

Sample Type: 2.5" X 6" TUBE

Description: SILTY SAND; light brown, fine, trace of clay & gravel.

LL= N/A

PI= N/A

Assumed Specific Gravity= 2.65

Remarks: Test Date: 10/25/2023

Client: Fairfax School District

Project: New District Office and MOT Yard

Source of Sample: B-2

Depth: 3'

Proj. No.: 19257




Date Sampled: 10/16/2023

DIRECT SHEAR TEST REPORT

SOILS ENGINEERING, INC.

Figure C-1

Tested By: DR



Sample No.		1	2	3
Initial	Water Content, %	6.7	6.6	6.2
	Dry Density, pcf	92.2	89.9	84.5
	Saturation, %	22.4	20.8	17.2
	Void Ratio	0.7946	0.8410	0.9571
	Diameter, in.	2.38	2.38	2.38
	Height, in.	1.00	1.00	1.00
At Test	Water Content, %	26.4	25.9	23.3
	Dry Density, pcf	92.2	89.9	84.5
	Saturation, %	88.0	81.7	64.5
	Void Ratio	0.7946	0.8410	0.9571
	Diameter, in.	2.38	2.38	2.38
	Height, in.	1.00	1.00	1.00
Normal Stress, ksf		1.00	2.00	4.00
Fail. Stress, ksf		0.80	1.24	2.59
Displacement, in.		0.15	0.18	0.24
Ult. Stress, ksf				
Displacement, in.				
Strain rate, in./min.		N/A	N/A	N/A

Sample Type: 2.5" X 6" TUBE
Description: CLAYEY SAND; light brown, fine, low plasticity.
LL= N/A **PI=** N/A
Assumed Specific Gravity= 2.65
Remarks: Test Date: 11/03/23

Client: Fairfax School District
Project: New District Office and MOT Yard
Source of Sample: B-4 **Depth:** 3'

Proj. No.: 19257 **Date Sampled:** 10/16/2023


DIRECT SHEAR TEST REPORT

SOILS ENGINEERING, INC.

Figure C-2

Tested By: DR **Checked By:** AL

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - Cal Test 301

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	350	123.0	8.7	0.00	25	2.47	398	71	71
2	350	120.1	9.7	0.00	30	2.55	285	69	69
3	350	122.5	10.8	0.00	38	2.51	181	63	63

Test Results	Material Description
R-value at 300 psi exudation pressure = 69	SILTY SAND; yellowish brown, trace of organic material & gravel.
Project No.: 19257 Project: New District Office and MOT Yard Location: R-1 Sample Number: 91070 Depth: 0-5' Date: 11/17/2023	Tested by: RC Checked by: AL Remarks: Test Date: 10/16/2023
R-VALUE TEST REPORT SOILS ENGINEERING, INC.	Figure D-1

R-VALUE TEST REPORT




Resistance R-Value and Expansion Pressure - Cal Test 301

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	350	116.0	14.0	0.39	67	2.55	440	40	40
2	300	115.2	14.5	0.18	80	2.55	339	33	33
3	270	113.7	15.0	0.09	90	2.52	262	27	27

Test Results	Material Description
R-value at 300 psi exudation pressure = 30 Exp. pressure at 300 psi exudation pressure = 0.04 psi	CLAYEY SILT; yellowish brown, trace of organic material & gravel.
Project No.: 19257 Project: New District Office and MOT Yard Location: R-2 Sample Number: 91071 Depth: 0-5' Date: 11/17/2023	Tested by: RC Checked by: AL Remarks: Test Date: 10/16/2023
R-VALUE TEST REPORT SOILS ENGINEERING, INC.	

Figure D-2

R-VALUE TEST REPORT



Resistance R-Value and Expansion Pressure - Cal Test 301

No.	Compact. Pressure psi	Density pcf	Moist. %	Expansion Pressure psi	Horizontal Press. psi @ 160 psi	Sample Height in.	Exud. Pressure psi	R Value	R Value Corr.
1	350	118.7	12.7	0.39	40	2.55	367	61	61
2	350	119.2	13.7	0.09	71	2.52	293	33	33
3	240	116.3	14.8	0.00	95	2.49	144	22	22

Test Results	Material Description
R-value at 300 psi exudation pressure = 35 Exp. pressure at 300 psi exudation pressure = 0.11 psi	SANDY SILT; dark yellowish brown, trace of clay & organic material.
Project No.: 19257 Project: New District Office and MOT Yard Location: R-3 Sample Number: 91072 Depth: 0-5' Date: 11/17/2023	Tested by: RG Checked by: AL Remarks: Test Date: 10/16/2023
R-VALUE TEST REPORT SOILS ENGINEERING, INC.	Figure D-3

APPENDIX D

SEISMIC DESIGN INFORMATION
SEAC Design Map Summary and Detail Report

EQFAULT
Version 3.00

California Fault Map

USGS web services were down for some period of time and as a result this tool wasn't operational, resulting in *timeout error*.
USGS web services are now operational so this tool should work as expected.



19257 New District Office and MOT Yard

Latitude, Longitude: 35.346238, -118.935456



Date	10/30/2023, 11:58:06 AM
Design Code Reference Document	ASCE7-16
Risk Category	II
Site Class	D - Stiff Soil

Type	Value	Description
S_S	0.962	MCE_R ground motion. (for 0.2 second period)
S_1	0.345	MCE_R ground motion. (for 1.0s period)
S_{MS}	1.073	Site-modified spectral acceleration value
S_{M1}	null -See Section 11.4.8	Site-modified spectral acceleration value
S_{DS}	0.715	Numeric seismic design value at 0.2 second SA
S_{D1}	null -See Section 11.4.8	Numeric seismic design value at 1.0 second SA

Type	Value	Description
SDC	null -See Section 11.4.8	Seismic design category
F_a	1.115	Site amplification factor at 0.2 second
F_v	null -See Section 11.4.8	Site amplification factor at 1.0 second
PGA	0.415	MCE_G peak ground acceleration
F_{PGA}	1.185	Site amplification factor at PGA
PGA_M	0.492	Site modified peak ground acceleration
T_L	12	Long-period transition period in seconds
S_{sRT}	0.962	Probabilistic risk-targeted ground motion. (0.2 second)
S_{sUH}	1.042	Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration
S_{sD}	1.5	Factored deterministic acceleration value. (0.2 second)
S_{1RT}	0.345	Probabilistic risk-targeted ground motion. (1.0 second)
S_{1UH}	0.376	Factored uniform-hazard (2% probability of exceedance in 50 years) spectral acceleration.
S_{1D}	0.6	Factored deterministic acceleration value. (1.0 second)
PGAd	0.5	Factored deterministic acceleration value. (Peak Ground Acceleration)

Type	Value	Description
PGA_{UH}	0.415	Uniform-hazard (2% probability of exceedance in 50 years) Peak Ground Acceleration
C_{RS}	0.922	Mapped value of the risk coefficient at short periods
C_{R1}	0.918	Mapped value of the risk coefficient at a period of 1 s
C_V	1.281	Vertical coefficient

DISCLAIMER

While the information presented on this website is believed to be correct, SEAOC / OSHPD and its sponsors and contributors assume no responsibility or liability for its accuracy. The material presented in this web application should not be used or relied upon for any specific application without competent examination and verification of its accuracy, suitability and applicability by engineers or other licensed professionals. SEAOC / OSHPD do not intend that the use of this information replace the sound judgment of such competent professionals, having experience and knowledge in the field of practice, nor to substitute for the standard of care required of such professionals in interpreting and applying the results of the seismic data provided by this website. Users of the information from this website assume all liability arising from such use. Use of the output of this website does not imply approval by the governing building code bodies responsible for building code approval and interpretation for the building site described by latitude/longitude location in the search results of this website.

```
*****
*                                     *
*   E Q F A U L T   *
*                                     *
*   Version 3.00   *
*                                     *
*****
```

DETERMINISTIC ESTIMATION OF
PEAK ACCELERATION FROM DIGITIZED FAULTS

JOB NUMBER: 19257

DATE: 10-30-2023

JOB NAME: New District Office and MOT Yard

CALCULATION NAME: Test Run Analysis

FAULT-DATA-FILE NAME: CGSFLTE.DAT

SITE COORDINATES:

SITE LATITUDE: 35.3462

SITE LONGITUDE: 118.9355

SEARCH RADIUS: 100 mi

ATTENUATION RELATION: 3) Boore et al. (1997) Horiz. - NEHRP D (250)

UNCERTAINTY (M=Median, S=Sigma): M Number of Sigmas: 0.0

DISTANCE MEASURE: cd_2drp

SCOND: 0

Basement Depth: 5.00 km Campbell SSR: Campbell SHR:

COMPUTE PEAK HORIZONTAL ACCELERATION

FAULT-DATA FILE USED: CGSFLTE.DAT

MINIMUM DEPTH VALUE (km): 0.0

EQFAULT SUMMARY

DETERMINISTIC SITE PARAMETERS

Page 1

ABBREVIATED FAULT NAME	APPROXIMATE DISTANCE mi (km)	ESTIMATED MAX. EARTHQUAKE EVENT		
		MAXIMUM EARTHQUAKE MAG. (Mw)	PEAK SITE ACCEL. g	EST. SITE INTENSITY MOD.MERC.
=====	=====	=====	=====	=====
Kern Front	8.5(13.6)	6.3	0.244	IX
WHITE WOLF	13.2(21.3)	7.3	0.301	IX
PLEITO THRUST	24.3(39.1)	7.0	0.163	VIII
GARLOCK (West)	32.4(52.2)	7.3	0.126	VIII
SAN ANDREAS - Whole M-1a	35.9(57.7)	8.0	0.169	VIII
SAN ANDREAS - Carrizo M-1c-2	35.9(57.7)	7.4	0.123	VII
SAN ANDREAS - 1857 Rupture M-2a	35.9(57.7)	7.8	0.152	VIII
SAN ANDREAS - Cho-Moj M-1b-1	35.9(57.7)	7.8	0.152	VIII
BIG PINE	36.5(58.7)	6.9	0.093	VII
SAN GABRIEL	43.8(70.5)	7.2	0.095	VII
SAN ANDREAS - Mojave M-1c-3	50.8(81.8)	7.4	0.094	VII
GARLOCK (East)	51.6(83.0)	7.5	0.098	VII
SAN ANDREAS - Cholame M-1c-1	52.5(84.5)	7.3	0.087	VII
SANTA YNEZ (East)	52.5(84.5)	7.1	0.078	VII
So. SIERRA NEVADA	55.2(88.9)	7.3	0.102	VII
SAN CAYETANO	57.1(91.9)	7.0	0.085	VII

M.RIDGE-ARROYO PARIDA-SANTA ANA	58.8(94.6)	7.2	0.092	VII
SAN JUAN	59.4(95.6)	7.1	0.071	VI
SANTA SUSANA	63.5(102.2)	6.7	0.066	VI
HOLSER	63.6(102.3)	6.5	0.060	VI
OAK RIDGE (Onshore)	65.9(106.1)	7.0	0.076	VII
NORTH CHANNEL SLOPE	65.9(106.1)	7.4	0.093	VII
NORTHRIDGE (E. Oak Ridge)	66.3(106.7)	7.0	0.075	VII
RED MOUNTAIN	66.7(107.3)	7.0	0.075	VII
LENWOOD-LOCKHART-OLD WOMAN SPRGS	66.7(107.4)	7.5	0.080	VII
SIMI-SANTA ROSA	68.4(110.1)	7.0	0.073	VII
VENTURA - PITAS POINT	68.7(110.6)	6.9	0.069	VI
SIERRA MADRE (San Fernando)	68.9(110.9)	6.7	0.062	VI
SANTA YNEZ (West)	69.3(111.5)	7.1	0.063	VI
LITTLE LAKE	71.1(114.4)	6.9	0.056	VI
GREAT VALLEY 14	72.8(117.2)	6.4	0.051	VI
OAK RIDGE MID-CHANNEL STRUCTURE	72.9(117.3)	6.6	0.057	VI
SAN LUIS RANGE (S. Margin)	76.0(122.3)	7.2	0.075	VII
VERDUGO	76.2(122.7)	6.9	0.064	VI
CHANNEL IS. THRUST (Eastern)	76.7(123.4)	7.5	0.088	VII
SIERRA MADRE	79.2(127.5)	7.2	0.073	VII
OWENS VALLEY	79.3(127.6)	7.6	0.074	VII
LOS ALAMOS-W. BASELINE	80.5(129.6)	6.9	0.061	VI
SAN ANDREAS - Parkfield	81.8(131.7)	6.5	0.040	V
ANACAPA-DUME	82.4(132.6)	7.5	0.083	VII

DETERMINISTIC SITE PARAMETERS

Page 2

ABBREVIATED FAULT NAME	APPROXIMATE DISTANCE mi (km)	ESTIMATED MAX. EARTHQUAKE EVENT		
		MAXIMUM EARTHQUAKE MAG.(Mw)	PEAK SITE ACCEL. g	EST. SITE INTENSITY MOD.MERC.
=====	=====	=====	=====	=====
OAK RIDGE(Blind Thrust Offshore)	83.0(133.6)	7.1	0.067	VI
HELEDALE - S. LOCKHARDT	83.2(133.9)	7.3	0.061	VI
GRAVEL HILLS - HARPER LAKE	83.7(134.7)	7.1	0.054	VI
LIONS HEAD	84.8(136.4)	6.6	0.050	VI
BLACKWATER	86.1(138.6)	7.1	0.053	VI
LOS OSOS	87.1(140.2)	7.0	0.061	VI
MALIBU COAST	87.3(140.5)	6.7	0.052	VI
GREAT VALLEY 13	87.7(141.2)	6.5	0.047	VI
CLAMSHELL-SAWPIT	88.4(142.2)	6.5	0.046	VI
CASMALIA (Orcutt Frontal Fault)	88.6(142.6)	6.5	0.046	VI
RINCONADA	88.7(142.8)	7.5	0.064	VI

HOLLYWOOD	88.9(143.0)	6.4	0.044	VI
UPPER ELYSIAN PARK BLIND THRUST	90.4(145.5)	6.4	0.043	VI
SANTA MONICA	91.0(146.4)	6.6	0.048	VI
PUENTE HILLS BLIND THRUST	91.4(147.1)	7.1	0.062	VI
RAYMOND	91.7(147.6)	6.5	0.045	VI
INDEPENDENCE	92.9(149.5)	7.1	0.061	VI
TANK CANYON	94.0(151.3)	6.4	0.042	VI
NEWPORT-INGLEWOOD (L.A.Basin)	95.1(153.1)	7.1	0.049	VI
PALOS VERDES	98.7(158.9)	7.3	0.053	VI
SANTA CRUZ ISLAND	99.2(159.7)	7.0	0.055	VI

-END OF SEARCH- 61 FAULTS FOUND WITHIN THE SPECIFIED SEARCH RADIUS.

THE Kern Front FAULT IS CLOSEST TO THE SITE.
IT IS ABOUT 8.5 MILES (13.6 km) AWAY.

LARGEST MAXIMUM-EARTHQUAKE SITE ACCELERATION: 0.3014 g

CALIFORNIA FAULT MAP

New District Office and MOT Yard

