

SECTION 32 3300

SITE FURNISHINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes: Provide the following site furnishings, including accessories, as required for complete, finished installation.
 - 1. Benches
 - 2. Trash & Recycle Containers
 - 3. Picnic Tables
 - 4. Prefabricated Restroom
 - 5. Playground Equipment
 - 6. Splash Pad Equipment

1.2 RELATED SECTIONS:

- A. Division 01 General Requirements, which contain information and requirements that apply to the work specified herein.

1.3 SUBMITTALS

- A. General: Submittals to be in accordance with the requirements of the Standard Specifications. Review or acceptance, as specified, by the Engineer required prior to commencement of work.
- B. Product Data: Submit manufacturer's product data, storage and handling requirements and recommendations, installation methods and available colors, styles, patterns, and textures for all site furnishings listed.
- C. Warranty: Manufacturer's standard warranty.

1.4 QUALITY ASSURANCE

- A. Workmanship and Materials: All workmanship and materials within this Section shall conform strictly to the manufacturer's specifications installation instructions and guarantees.
- B. The contractor shall provide laborers and supervisors who are thoroughly familiar with the type of construction involved and materials and techniques specified.
- C. Contractor shall provide a GameTime® Certified Installer to oversee and direct the proper installation of the play equipment. If contractor does not have a Certified

Installer at the time of Bid Opening, the Certified Installer may become certified subsequent to Notice to Proceed; however, such certification process must be accomplished within the same Contract Time, and at no additional cost of time extension to the County.

1.5 SUBSTITUTIONS, ADDITIONS AND DELETIONS

- A. General: Submit proposals for substitutions for review and approval. Acceptance by the County is required prior to proceeding with the work under this Section. Provide descriptive catalog literature for each item to be substituted.

1.6 PRODUCT DELIVERY, STORAGE AND HANDLING

- A. Handling of site furnishings: The Contractor is cautioned to exercise care in handling, loading, unloading, storing and installation of site furnishings. All materials shall be transported in a vehicle that allows the materials to lie flat, not to subject it to undue bending or concentrated external load at any point. Any materials that have been dented or damaged will be discarded and, if installed, shall be replaced.
- B. Upon receipt at the job site, all materials shall be checked to ensure that no damages occurred during shipping or handling. Materials shall be stored in such a manner to ensure proper ventilation and drainage, and to protect against damage, weather, vandalism, or theft.

PART 2 - PRODUCTS

2.1 BENCHES

- A. Kings River Casting, 1350 North Ave., Sanger, CA 93657, or approved equal
Phone: (888) 545-5157. Website www.kingsrivercasting.com

Bench: 24.5" x 72.5" x 32", "Iron Valley Slatted" Bench (Model IVSBC-72"), Slats: Aluminum Extrusion, Arms: end and center. Finish: primer powder-coated, and final coat electrostatically powder coated - Color: Evergreen

Mounting: Surface Mounted, bolt to concrete pad with corrosion resistant hardware to be supplied by contractor.

2.2 TRASH AND RECYCLE CONTAINERS: 1 OF EACH (T.+R.) AT EACH LOCATION SHOWN ON PLAN

- A. Kings River Casting, 1350 North Ave., Sanger, CA 93657, or approved equal
Phone: (888) 545-5157. Website www.kingsrivercasting.com

Containers: 26" x 36", 55 Gallon Trash Receptacle - expanded metal (Model - EMTR-55). Finish: primer powder coated, and final coat electrostatically powder-coated - Color: Evergreen for trash container and Blue for Recycle container.

Mounting: Surface Mounted, Bolt to concrete pad with corrosion resistant hardware to be supplied by contractor.

Top #1 - Order with optional Dome Top. Provide painted sign on dome in white letters: LANDFILL. Letters to be 2" to 2.5" tall.

Top #2 - Order with optional Dome Top. Provide painted sign on dome in white letters: RECYCLE. Letters to be 2" to 2.5" tall.

2.3 PICNIC TABLES

- A. Kings River Casting, 1350 North Ave., Sanger, CA 93657, or approved equal
Phone: (888) 545-5157. Website www.kingsrivercasting.com

Picnic Table: 68" x 72", Expanded Metal Picnic Table - Steel (Model EMTP-6). Steel pipe supports and 3/4" #9 expanded metal fully welded diamond patterned slats. Finish: primer powder coated, and final coat electrostatically powder-coated - Color: Evergreen slats, Black supports.

Mounting: surface mounted with surface clamps set in the concrete. Bolt in place with lock washers. Contractor to provide attachment hardware. Provide a submittal of the hardware.

2.4 PREFABRICATED RESTROOM

Refer to specification section 13 1200 - Precast Concrete Restroom Building for contractor supplied and installed restroom specification.

PLAYGROUND EQUIPMENT

- 2.5 Game Time equipment coordinated through Great Western Recreation, Job # 107394-01
Contact: Tyler Kyriopoulos (435) 760-5103 (tyler@gwpark.com) or approved equal
Website www.gametime.com

Installation of all playground equipment: per manufacturer's specifications.

SPLASH PAD EQUIPMENT

- 2.6 Water Odyssey Splash Pad equipment coordinated through Fountain People, Job # W24084
Contact: Jim Hartman (512) 781-6375 (jim.hartman@fountainpeople.com)
Website www.fountainpeople.com

Installation of all splash pad equipment: per manufacturer's specifications.

SPLASH PAD EQUIPMENT ENCLOSURE

- 2.7 AquaWorx standalone cabinet (model #AWCB-1) coordinated through Great Western Recreation, Job # 107394-01
Contact: Tyler Kyriopoulos (435) 760-5103 (tyler@gwpark.com) or approved equal
Website www.gametime.com

Installation of cabinet: per manufacturer's specifications.

PART 3 - EXECUTION

3.1 GENERAL

- A. Handle and install site furnishings in accordance with manufacturer's approved shop drawings and instructions.
- B. Deliver manufactured furnishings in original packaging. Protect and secure furnishings delivered to site from damage and theft.

3.2 SITE FURNISHINGS

A. Layout of Site Furnishings

- 1. Layout: Layout site furniture according to the locations shown on the drawings, and as required by the Engineer.
- 2. Examination: Examine areas to receive site furnishings. Notify Engineer of conditions that would adversely affect installation or subsequent use. Do not begin installation until unacceptable conditions are corrected.
- 3. Adjustments: The Engineer reserves the right to make adjustments in the locations of the site furniture without additional cost to the County.
- 4. Quantity of furnishings shall be as specified on plans and in these specifications.

B. Installation of Site Furnishings

- 1. Surface mount furnishings per manufacturer's specifications and as specified on plans.
- 2. Set site furnishings level and true to line, in correct relationship to adjacent materials.
- 3. Bolt down in place or secure by other means all furnishings, as indicated in these specifications.
- 4. Prepare subgrade and utility stubs for the prefabricated restroom per manufacturer's instructions.
- 5. Install all play equipment according to the manufacturer's specifications, including installation of signage that comes with the purchase of the equipment.
- 6. Install all splash pad equipment according to the manufacturer's specifications and connect to potable water and wastewater systems.

C. Cleaning:

- 1. The contractor shall clean the jobsite of excess materials and any debris that is caused by surface mounting.
- 2. Clean furnishings promptly after installation in accordance with manufacturer's

instructions.

3. Do not use harsh cleaning materials or methods that could damage finish.

3.3 FINAL ACCEPTANCE

- A. Final Acceptance shall be when all furnishings and fixtures are installed in accordance with approved Drawings and to manufacturer's specifications, and all damaged parts and items are replaced.
- B. Submit product maintenance data.

END OF SECTION